BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work: Improvements to Cross & Main Roads at Shettyhalli Gate Palya, in Shettyhalli Sub Division, Ward No-12.

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Sqm	878.08	87.05	Rupees Eighty Seven and Four Paise Only
2	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed. complete as per specifications.	Cum	1294.73	120.96	Rupees One Hundred Twenty and Ninety Six Paise Only
3	Providing granite slabs of selected quality roughly dressed &7 fixed in cement mortar (1:6) including fixing curing etc. complete as per specifications.	Sqm	3225.60	327.24	Rupees Three Hundred Twenty Seven and Twenty Four Paise Only
4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Complete as per Specification.	Cum	683.94	1194.48	Rupees One Thousand One Hundred Ninety Four and Forty Eight Paise Only
5	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Complete as per Specification.	Cum	455.96	1366.20	Rupees One Thousand Three Hundred Sixty Six and Twenty Paise Only

Technical Manager-2C
KRIDL, BBMP, Bangalore

Signature of the Contractor

Executive Engineer

6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading. complete as per specifications.	Cum	2113.00	100.35	Rupees One Hundred and Thirty Five Paise Only
7	Carriage of mixed materials 10 Kms, complete as per specifications.	Rmtr	1139.90	52.11	Rupees Fifty Two and Eleven Paise Only

Signature of the Contractor

Technical Manager
KRIDL, BBMP, Ltd.

Executive Engineer,
Dasarahalli Division,